Sl. No.	Items of work	Per	Quantity	Rate
20	Providing and fixing rectangular cast iron rain water down take pipes with heads and bends, embedded in masonry, etc., complete	R.ft.	390	1 6 0
21	Providing 4½" thick exmet wall in burnt brick in cement mortar exmet reinforcements at every 3rd course with cement mortar plastering and white washing, etc., complete	S.ft.	921	0 10 0
22	Teakwood staircase with turned balusters with steps 4½ feet wide 12" tread including ¾" nosing and 6" wide with ¾" planks for platform and ceiling finished with "Dulux" varnish	S.ft.	..	..
23	Teakwood spiral stair case of 5 feet dia. with necessary railings, etc., complete to a floor of 10 feet in height	Each	2	*100 0 0
24	Cast iron spiral stair case of 4½' diameter with necessary cast iron railings providing and fixing, etc., complete to a floor of 10 feet in height	,,	2	*100 0 0
25	Roofing with reinforced concrete slab 5" thick with 3" kappi and 2 courses of flat tiles and plastering at top and bottom etc., complete	Sqrs.	..	..

* Per running foot height to be quoted.

M. N. LAKSHMAN RAO,
Executive Engineer.

CHITALDRUG DIVISION.

Notification dated 30th July 1940.

1. Sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 12 noon on 23rd August 1940, for the construction of an additional Tuberculosis Ward at Davangere.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Chitaldrug Division, should be addressed to the Executive Engineer, Chitaldrug Division, in a sealed cover and superscribed as "Tender for contruction of an additional Tuberculosis Ward at Davangere." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a Treasury chellan for earnest money of Rs. 250 paid to the Treasury to the credit of "17(*a*). P. W. Deposits" against the account of the Executive Engineer, Chitaldrug Division. The earnest money of the successful tenderer will be retained as security for due fulfilment of the contract. Such a deposit will not carry any interest.

4. The tenders will be opened in the presence of such tenderers as wish to be present on 23rd August 1940 at 4 P.M. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental Schedule Contract Form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay Specifications (1931).

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Chitaldrug, on all working days between 11 A.M. and 5 P.M. and may be obtained from that officer on payment of Rs.....

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of January 1941, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 10 per day, which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.

(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.

(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.

(4) Arrange for protecting work during inclement weather.

(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.

(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.

(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.

(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.

(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.

(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

23. "Chamundi Brand" Cement alone should be used.

24. Items not provided for in the estimate and items for which lumpsum prvision is made, will be paid as per lowest schedule of rates.

Detailed estimate for the construction of a "Tuberculosis Ward" at Davanagere.

Sl. No.	Details of wrok	Unit	Quantity	Rate	Tender rates in	
					Figures	Words
				Rs. a. p.	Rs. a. p.	
1	Earthwork excavation for foundation and filling in basement ..	C.yd.	117	0 5 0		
2	Lime and jelly concrete for foundation	C.ft.	578	0 3 0		
3	Size stone in lime mortar ..	,,	2,534	0 4 0		
4	Burnt brick in lime mortar ..	,,	1,804	0 4 0		
5	Burnt brick in cement mortar ..	,,	65	0 8 0		
6	Burnt stone slabs 6″ thick dressed 2 lines and fixed in mortar ..	S.ft.	429	0 7 0		
7	Burnt stone slabs 6″ thick dressed and fixed	,,	60	0 7 0		
8	Cement concrete slabs 3″ thick ..	,,	425	0 12 0		
9	R. C. lintels slabs 9″ thick ..	C.ft.	36	2 4 0		
10	R. C. chajja 3″ to 6″ thick as per approved design	S.ft.	459	0 12 0		
11	Cement concrete pillars of 1′–4″ base and 1′–2″ top with base and capital, etc.; complete	No.	13	15 0 0		
12	T. W. battened doors with necessary iron fittings, wood oiling, etc., complete	S.ft.	117	1 5 0		
13	T. W. windows with battened shutters, and iron fittings and wood oiling, etc., complete	S.ft.	126	1 8 0		
14	R. C. ventilators of approved design.	,,	63	1 0 0		
15	R. S. girders tested including hoisting, fixing and 2 coats of anti-corrosive paint	Cwt.	19	13 0 0		
16	R. C. joist terrace roofing of approved design and specification with brick nogging 2 courses of flat tiles over 3″ lime concrete bed and plastering top ceiling, etc., complete ..	Sqr.	15.17	60 0 0		
17	Lime mortar plastering	,,	30.40	3 4 0		
18	Cement plastering ½″ thick and finished smooth	,,	3.06	8 0 0		
19	Dadooing with glazed tiles ..	,,	4.70	50 0 0		
20	Whitewashing	,,	30.40	0 4 0		
21	Parapet wall 9″×1½′ with cornice, plastering, etc., complete ..	R.ft.	220	0 8 0		
22	Cement concrete flooring 1″ thick over 3″ concrete bed with ½″ to ¾″ cement plaster in red cement ..	Sqr.	12.49	18 0 0		
23	Cement pointing	,,	2.83	3 6 0		
24	Providing movable wooden screens ..	S.ft.	84	0 8 0		
25	Boxing girders in cement concrete and nice plastering	R.ft.	116	0 6 0		
26	Providing Sanitary fittings	L.S.	..	100 0 0		
27	Providing lead off drains	,,	..	20 0 0		
28	Providing sinks and baths	Each	2	18 0 0		
29	Painting doors and windows with green paint 2 coats	Sqr.	4.86	4 0 0		

B. TIRUMALACHAR,
Executive Engineer.